

15-077-10047-00 00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper County, Sec. 20 Twp. 31 Rge. 7 (E) 7 (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SE

Lease Owner Continental Oil Company

Lease Name T. S. Hudson Well No. 2

Office Address Box 161, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-14 19 57

Application for plugging filed 9-16 19 57

Application for plugging approved 9-15 19 57


Plugging commenced 9-15 19 57

Plugging completed 9-15-57 19

Reason for abandonment of well or producing formation No commercial zones encountered.

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Simpson Sand Depth to top 4733 Bottom _____ Total Depth of Well 4800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Simpson Dolomite</u>	<u>Oil, gas, & water</u>	<u>4710</u>	<u>4730</u>	<u>8 5/8"</u>	<u>250'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 4750' of drill pipe in hole and cemented from 4750 to 4730 with 24 sacks of cement. Let cement set 3 hrs. pulled drill pipe to 4370 and spotted 15 sacks of cement from 4370 to 4330. Let cement set 3 hrs. Pulled drill pipe to 2600 and pumped mud into formation and emptied mud pits. Pulled drill pipe from hole and set 8 7/8" plug at 225'. Dumped 20 sacks of cement on plug. Set an 8 7/8" plug at 35' and dumped 1/3 sack of hulls and 10 sacks cement on top of plug. Well plugged and abandoned at 5:30 a.m. on 9-15-57. Service Company - Halliburton.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Michaelis Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton
F. L. Dunn (employee of owner) or Notary Public of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC 9-16-57 (Signature) F. L. Dunn (Dist. Supt.)

State RFD Sohio File Box 161, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September 19 57

My commission expires 12-4-57 James W. Bolick Notary Public.

24-7368-5 3-53-20M

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1957

PLUGGING
FILE SEC. 20 T. 31 R. 7W
BOOK PAGE 45 LINE 34

T.S. HUDSON #2

Well Record

Location: Section 20-318-7W
Harper County, Kansas

Commenced: August 22, 1957
Completed: September 14, 1957
(Rotary)

Operator: Continental Oil Company
Box 161
Great Bend, Kansas

Contractor: Graham-Michaelis Drilling Co.
211 North Broadway
Wichita, Kansas

Casing Record: 8 5/8" @253' W/200 sacks cement

LOG

Sub Soil, Clay & Sand	20
Clay, Sand, Shale & Red Bed	427
Shale & Shells	555
Shale, Anhydrite Streaks	1145
Shale-Lime	1385
Shale & Lime Shells	1530
Bro. Lime & Shale	1665
Lime Shale	1797
Shale & Lime	1895
Lime & Shale	3538
Lime, Shale, Sand	3729
Shale-Lime	3855
Lime	3906
Lime & Shale	3935
Lime	3992
Lime & Shale	4123
Lime	4158
Lime & Shale	4342
Coring	4362
Cherty Lime & Shale	4420
Lime, Cherty	4483
Chirt	4520
Cherty Lime & Shale	4553
Chert	4561
Chirt	4584
Chirt & Shale	4640
Shale-Bro. Lime	4683
Lime	4700
Lime-Chirt	4705
Coring	4728
Coring Sand	4733
Coring	4740
Sand	4754
Lime & Shale	4773
Sand, Shale & Lime	4800, RTD.

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1957

STATE OF KANSAS)
) ss. CONSERVATION DIVISION
COUNTY OF SEDGWICK)

PLUGGING
FILE SEC 20 T.31 R.7W
BOOK PAGE 45 LINE 34

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

Subscribed and sworn to before me
this 20th day of Sept. 1957.

GRAHAM-MICHAELIS DRILLING CO.

By John L. James
John L. James, Geologist.

J. D. Grier

My commission expires: 1/7/61.

SCC RFD (H) PJH FILE