

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-077-19001-00-2100 well
API NUMBER 11-27-59

LEASE NAME Woods

WELL NUMBER #2

1980 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 5 TWP. 31 RGE. 8 ~~XXXXX~~

COUNTY Harper

Date Well Completed 11-27-59

Plugging Commenced 11-17-00

Plugging Completed 11-21-00

03-02-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R & B Oil & Gas, Inc.

ADDRESS PO Box 195, Attica, KS 67009

PHONE#(316 254 7251) OPERATORS LICENSE NO. 31191

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-17-00 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Mississippi Depth to Top 4432 Bottom 4457 T.D. 4492

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	200'	
MISS	oil & Gas			4 1/2	4492'	2541'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded Bottom. Bailed 45 sacks of Portland, shot 2,719, worked pipe. Shot at 2541'. Pulled to 1,250', pumped 35 sacks. Pulled to 850'. Pumped 35 sacks. Pulled to 300'. Circulated cement to surface with 140 sacks. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 31925

Address 415 E Main St, Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.


STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above described well as filed the same are true and correct, so help me God.

(Signature) Randy Newberry

(Address) PO Box 195, Attica, KS 67009



SUBSCRIBED AND SWORN TO before me this 20th day of February, 2001

Rebecca S. Newberry Notary Public

My Commission Expires: 7-21-2001

SERVICE TICKET

UNITED CEMENTING & ACID CO., INC.

2368

BOX 712

EL DORADO, KANSAS 67042

PHONE AC 316-321-4680

DATE 11-21-00 COUNTY Harper
 CHG. TO: R+B Oil + Gas ADDRESS P.O. Box 195
 CITY Attica STATE Kansas ZIP 67009
 LEASE & WELL NO. Woods # 2 SEC. 5 TWP. 31 RNG. 6
 CONTRACTOR Quality Well TIME ON LOCATION 8:00A
 KIND OF JOB Old Hole Plug

SERVICE CHARGE: 450.00

QUANTITY	MATERIAL USED	TYPE		
2100#	60/40 ppg	@	4.70	987.00
8#	Gal	@	9.50	76.00
218#	BULK CHARGE	@	.89	194.02
96	BULK TRK. MILES	(Chy for 60 miles x 66 x 11 tons)		435.60
96	PUMP TRK. MILES	one way @ 200 per mile		192.00
	PLUGS	<u>None</u>		
	SALES TAX			137.74
	TOTAL			2,472.36

T. D. 4492 CSG. SET AT 4492 VOLUME _____
 SIZE HOLE 7 7/8 TBG SET AT _____ VOLUME _____
 MAX. PRESS. _____ SIZE PIPE 4 1/2 9.5# Recover 252
 PLUG DEPTH 1250-850-300 PCKER DEPTH 8 5/8 200'
 PLUG USED _____ TIME FINISHED 10:30A

REMARKS: Via 4 1/2 Lead Hole + Circulate - Spot 35# @ 1250'
Spot 35# @ 850'
Circulate to Surface + Fill Celler from 300' with
140# - Pull Csg Celler Remained full
Used 210# 60/40 ppg 48 Gal

EQUIPMENT USED

NAME <u>Chat Johnson</u>	UNIT NO. <u>14</u>	NAME _____	UNIT NO. <u>1</u>
<u>Neal</u>			

CEMENTER OR TREATER _____ OWNER'S REP. _____