

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
12-15-80  
RECEIVED  
STATE CORPORATION COMMISSION  
SEP 1 1982  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Harper SEC. 5 TWP. 31S RGE. 8W E/W  
Location as in quarters or footage from lines:  
100 - South of NE NE SE


Lease Owner McCoy Petroleum Co.  
Lease Name Gill Well No. B-2  
Office Address One Main Place, Suite 410, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed 1-20-82  
Application for plugging filed 8-20-82  
Plugging commenced 8-24-82  
Plugging completed 8-30-82  
Reason for abandonment of well or producing formation Dry

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. L. Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4501

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	265	None
				4 1/2	4501	3820

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plug back at 4475  
Sand from 4475' to 4430'  
4 sacks from 4430' 50 4400'  
Ripped at 3820'  
Dowell pumped in 15 sacks jell - 6 sacks hulls, 10 sacks jell  
150 sacks common cement 3% c.c.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Harper, ss.  
Elmer R. Morgenstern (employee of owner) or (owner or operator) of the  
above-described well, being first sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Morgenstern  
Medicine Ridge, Mo.  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August 1982

Jessie Hamilton  
Notary Public.

My Commission expires: April 4, 1986.



Natural Gas • Crude Oil  
Exploration & Production

**McCOY PETROLEUM CORPORATION**

One Main Place / Suite 410 Wichita, Kansas 67202

John Roger McCoy  
President

316-265-9697

Harvey H. McCoy  
Vice-President

DAILY REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1982

CONSERVATION DIVISION  
Wichita, Kansas

McCoy Petroleum Corporation  
#2 Gill "B"  
100' South of NE NE SE  
Section 5-31S-8W  
Spivey-Grabs Field  
Harper County, Kansas  
API # 15-077-20,760

Contractor: Sweetman Drilling, Inc.  
Geologist: Robert E. McCann

Elevations: 1667 KB 1664 DF 1657 GL

12-14-81 Move in Rotary Tools. Rig up. Spud @ 3:00 P.M. Set new 8-5/8" OD, 24# surface casing @ 265'. Halliburton cemented with 250 sacks of common cement, 2% gel, 3% calcium chloride. Cement circulated. P.D. @ 8:00 P.M.

12-15-81 Drilling @ 506'.

SAMPLE TOPS

12-16-81 Drilling @ 1835'.

Heebner 3428(-1761)

12-17-81 Drilling @ 2686'.

Lansing 3623(-1956)

12-18-81 Drilling @ 3516'.

Stark 4066(-2399)

12-19-81 Drilling @ 4253'.

Cherokee 4312(-2645)

12-20-81 Taking DST #1 @ 4465'.

Mississippian 4423(-2756)

RTD 4500(-2833)

DST #1 4445-4465' (Mississippian)

Open 30", S.I. 45", Open 60", S.I. 60"

Strong blow throughout test.

Recovered 302' of fluid as follows:

62' of gas cut mud,

120' of slightly oil & gas cut mud,

60' of oil & gas cut mud,

60' of oil & gas cut watery mud (39,000 ppm chlorides)

ISIP 729# FSIP 676#

IFP 129-118# FP 139-124#