


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 5 Twp. 31S Rge. 8W (E) (W)

Location as "NE/CNWxSWx" or footage from lines. NE/NE/SW
Lease Owner: Mull Dilling Company
Lease Name: Wood Well No. 1
Office Address: 6405 East Kellogg Street, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 3-1 1957
Plugging completed _____ 3-6 1957
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4428' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,659'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 4428'.
Plugging started 3-1-57. Finished 3-6-57.
Plugged off bottom with s and to 4400' and dumped 5 sacks cement with bailer.
Shot 5 1/2" casing at 3,659'. Pulled pipe out of hole and plugged well with heavy mud to 200' and set permanent rock bridge. Dumped 25 sacks cement.
Filled hole with heavy mud to 35' and mixed 10 sacks cement for cap on well.

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 - 1957
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1957.

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 5 T 31 R 8W
BOOK PAGE 143 LINE 34

ROTARY DRILLERS LOG

COMPANY : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMMENCED: 8-15-55
 Wichita, Kansas

CONTRACTOR : Purcell-Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 8-27-55
 Wichita, Kansas

CASING RECORD: Set 8 5/8" Surf. Csg. @ 165' cemented with 150 sacks cement.
 Set 5 1/2" Csg. @ 4426' cemented with 150 sacks cement.

LOCATION: WDM #1
 NE NE SW of 5-318-8W
 Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sand & Clay	110	Lime	3560
Red Rock	165	Lime & Shale	3996
Red Bed, Shale & Shells	765	Lime	4014
Shale & Shells	1410	Lime & Shale	4091
Lime & Shale	2200	Lime	4142
Shale & Lime	2905	Lime & Shale	4214
Lime & Shale	3191	Shale & Lime	4404
Sand, Shale & Lime	3635	Lime (Miss)	4426 N.T.D.
Shale & Lime	3700		

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Mull Drilling Co., Inc.

Francis H. Purcell
 FRANCIS H. PURCELL, SECRETARY

STATE OF KANSAS)
) SS
 COUNTY OF SEDWICK)

Subscribed and sworn to before me this 29th day of August, 1955

Ethel Zimmerman
 Notary Public

MY COMMISSION EXPIRES: January 24, 1957

PLUGGING
 FILE SEC 5 T 31 R 8 W
 BOOK PAGE 143 LINE 34

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 26 1957
 CONSERVATION DIVISION
 Wichita, Kansas