

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30525
Name: D.S. LANGSTON
Address 1: 310 W. CENTRAL, STE.#202
Address 2:
City: WICHITA State: KS Zip: 67202 + 1004
Contact Person: DAVID S. LANGSTON
Phone: (620) 786-0874
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
L-KC Depth to Top: 2958 Bottom: 3200 T.D.
ARBUCKLE Depth to Top: 3253 Bottom: 3296 T.D. 3296 (OH)
Depth to Top: Bottom: ORIG 3276 T.D.

API No. 15 - 159-06548-00-00
Spot Description:
SE SE NW Sec. 31 Twp. 18 S. R. 10 East West
3,019 Feet from North / South Line of Section
3,141 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: RICE
Lease Name: REIF Well #: B-1
Date Well Completed: 1/17/1951
The plugging proposal was approved on: 12/05/2012 (Date)
by: VIRGIL CLOTHIER (KCC District Agent's Name)
Plugging Commenced: 1/08/2013
Plugging Completed: 1/11/2013

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8.625"	311'	0
		PRODUCTION	5.5"	3253'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Copeland Acid & Cement (Field Order Ticket C # 38143); plugged hole with 60/40 Poz Mix 2% Gel cement as follows: 1/9/13- washed sand down to 2200' & spotted 5 sx cement, perf. @ 1250', 850', 360' & pumped 35 sx @ 1261'. Next day on 1/11/13 tagged cement @ 950', spotted 35 sx @ 850', spotted 160 sx @ 350', topped off with 20 sx.

Copeland Acid & Cement then came back on 1/22/13 (Field Order Ticket C# 38232) and topped off with an additional 20 sx of 60-40 Poz Mix to bring cement to surface after natural settling. See invoices attached.

Plugging Contractor License #: 3004 99981 Name: COPELAND ACID & CEMENT
Address 1: BOX 438 Address 2:
City: HAYSVILLE State: KS Zip: 67060 + 0438
Phone: (316) 525-1225
Name of Party Responsible for Plugging Fees: D.S. LANGSTON (\$107.06 fee already paid by operator's check #7542)

State of KS County, Sedgwich, ss.
D.S. LANGSTON Employee of Operator or Operator on above-described well,

(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 13 2013
KCC WICHITA *de*