

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-191-20590-0090

LEASE NAME WYCKOFF

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER "A" #1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 12 TWP. 33 RGE. 2W (E) or (W)

COUNTY SUMNER

LEASE OPERATOR JOHNSON OIL FIELD SERVICE, INC.

ADDRESS RR 1, WELLINGTON, KS 67152

PHONE# (316) 326-5731 OPERATORS LICENSE NO. 7233

Date Well Completed 6/76

Character of Well OIL

Plugging Commenced 2/12/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/14/91

The plugging proposal was approved on 2/12/91 (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? No

Producing Formation SIMP Depth to Top 4232 Bottom 4234 T.D. 4315

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
SURFACE		0	404	8 5/8	404	0
simpson		0	4314	4 1/2	4314	2792

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand back to 4175. Dump 4 sx cmt with dump bailer. Mud to 465'. Cut pipe @ 2792'. Pull pipe. Ran 465' 2 3/8" tubing. Set 35 sx plug. Mud to 60 ft. Circulate cut to surface. Pull tubing. Top off with cmt. United Cementing & Acid Co., Inc. 60/40 Pozmix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor LYONS WELL SERVICE License No. 30375

Address 1103 S. St. John, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JOHNSON OIL FIELD SERVICE, INC.


STATE OF KANSAS COUNTY OF SUMNER, ss.

Willis Lowe (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Willis Lowe

(Address) RR 1, Wellington, KS 67152

SUBSCRIBED AND SWORN TO before me this 13 day of March, 19 91



Doug Norris Notary Public
 Expires: 3-2-92

RECEIVED
 STATE OF KANSAS COMMISSION
 MAR 14 1991
 Form CP-4
 Revised 05-88
 WICHITA DIVISION
 Wichita, Kansas