

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Barber

Location: 990' fr E. 2310 fr W. Sec. 20 Twp. 31 Rge. 7 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4783

I have this date completed supervision of plugging of:

Lease Name: T. S. Hudson Well No. 3

Operator's Full Name: Continental Oil Co

Complete Address: Bex 161, Great Bend, Kans.

Plugging Contractor: Garvy Drilling Co.

Address: Great Bend, Kans. License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4:30AM Day 17 Month October Year 1958

The above well was plugged as follows:

260' of 8 5/8" surface casing circulated with cement. 30 sack cement  
spotted on bottom. Hole was filled to 250' with heavy drilling mud.  
Cementing plug with 1/4 sack hulls below plug and 20 sack cement placed  
through drill pipe from 250'. Heavy drilling mud to 40' with cementing  
plug and 20 sack cement to base of cellar. Steel cap welded top pipe.

Signed:   
Conservation Division Agent

Reviewed:   
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 20 T. 31 R. 7W  
BOOK PAGE 137 LINE 19

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1958  
CONSERVATION DIVISION  
Wichita, Kansas