

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Continental Oil Co.
Complete Address 3535 NW 58th St Oklahoma City, OK
Lease Name T.S. Hudson Well No. 7
Location SW/SW/SE Sec. 20 Twp. 31 Rge. 7 (E) (W) W
County Harper Total Depth 4750
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Rockhold Engineering Inc
Address Box 698 Great Bend, KS License No. 637
Operation Completed: Hour 3:00 PM Day 21 Month 3 Year 1973

The above well was plugged as follows:

255 ft 8 5/8 surface cemented with 200 sacks. 4749 ft 5 1/2 long string
cemented with 250 sacks. Top perf. 4698 ft. Sand to 4600 ft, 5
sacks cement with bailer. Pulled 2000 ft 5 1/2. Set 10 ft rock bridge
at 250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3-23-73
INV. NO. 2164-W