

15-077-10174-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 19 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Continental Oil Co  
Complete Address 3535 NW 58th St Oklahoma City, OK  
Lease Name T.S. Hudson Well No. 5  
Location NE/SE/SE Sec. 20 Twp. 31 Rge. 7 (E) (W) W  
County Harper Total Depth 4735  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Rockhold Engineering Inc  
Address Box 698 Great Bend, KS License No. 637  
Operation Completed: Hour 10:00 AM Day 16 Month 3 Year 1973

The above well was plugged as follows:

261 ft 8 5/8 surface cemented with 200 sacks. 4734 ft 5 1/2 long string  
cemented with 200 sacks. Top perf. 4684 ft. Sand to 4670 ft, 5 sacks  
cement with bailer. Pulled 2800 ft 5 1/2. Set 10 ft rock bridge at  
250 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3/19/73  
INV. NO. 7146-W