

RP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Kennedy Well No. # 1

Location SW SW SE Sec. 5 Twp. 31 Rge. 8 (E) (W)W

County Harper Total Depth 4438

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 11:30AM Day 4th Month Jan. Year 1964

The Above well was plugged as follows:

187' of 8 5/8" surface pipe, cemented with 175 sacks. 4410' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 4401'. Bottom of hole
was sanded to 4390', and cemented with 5 sacks. Fluid level was 230' in
hole. Plug was set at 230', 10' rock bridge, cemented with 30 sacks.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar. 3700' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/7/64
INV. NO. 8412-11