

2 040315

2-20-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-20,289 -00-00
SE, SEC. 20, T 31 S, R 7 W/EX
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146
Operator: Rains & Williamson Oil
Name & Address: 435 Page Court,
220 West Douglas
Wichita, KS 67202

Lease Name Hudson Est. Well # 1
County Harper 157.65
Well Total Depth 4666 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ellis County Drilling License Number

Address

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Paul Stephens

(company name) Rains & Williamson Oil Company, Inc. (phone)

were: 4 1/2" - 4663'

Open Hole - 4663-66

CIBP - 4580 with 3 sacks cement

4 Hulls, 15 Gel, 120 sacks cement

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:15 pm Day: 20 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT A bridge plug was set at 4580' and capped with three barrels of sand and three sacks of cement. The 5 1/2" was shot off and recovered from 3140'.

The tip was squeeze plugged by pumper, 4 sacks hulls, 15 sacks gel and 120 sacks of 60/40 poz cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 7 1987

Remarks: B.J. Titan #349941 Max-650# SI - 300#
Wichita, Kansas

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-8-87

INV. NO. 16521

WC

Signed (TECHNICIAN)