

2-010110

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

RCH 3-13-13

6-13

API NUMBER: 15-155-21,100-0000

C SW SE, SECTION 11 TOWNSHIP 23 RANGE 10W

OPERATOR LICENSE # 5447
OPERATOR OXY USA INC
NAME & 110 SOUTH MAIN, SUITE #800
ADDRESS WICHITA, KS 67202

660' 554 FEET FROM S SECTION LINE
1920' 1945 FEET FROM E SECTION LINE
LEASE NAME: TONN "A" #3
COUNTY: RENO 124, 31
WELL TOTAL DEPTH: 3825' (3812')
PIPE:
SURFACE CASING: 9 5/8" @ 257'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD

RECEIVED
KANSAS CORPORATION COMMISSION
8-13-96
AUG 13 1996

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: CLARK CORPORATION
ADDRESS: 107 WEST FOWLER, MEDICINE LODGE, KS 67104 LICENSE: 5105
CONSERVATION DIVISION
WICHITA, KS

COMPANY TO PLUG AT: HOUR: 10:55 DAY: 13 MONTH: 6 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: LANCE FETTHOELTER

COMPANY NAME: OXY USA INC. PHONE: (316) 672-5630

WERE: SET CIBP AT 3740' AND TOP WITH 2 SACKS OF CEMENT. SHOOT PIPE OFF AND PULL TO 1400'. SPOT 35 SACKS OF CEMENT. PULL PIPE TO 900' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 307' AND CIRCULATE CEMENT TO THE SURFACE.

CIBP AT 3773' 7" CASING AT 3824' PERFORATIONS AT 3749' TO 3750'

PLUGGING PROPOSAL RECEIVED BY: R. PHIL WORLEY

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:45 DAY: 13 MONTH: 6 YEAR: 1996

ACTUAL PLUGGING REPORT: SAT CIBP AT 3740' AND TOPPED WITH 2 SACKS OF CEMENT. SHOT PIPE OFF. PULLED PIPE TO 1400' AND SPOTTED 35 SACKS OF CEMENT. PULLED PIPE TO 900' AND SPOTTED 35 SACKS OF CEMENT. PULLED PIPE TO 310' AND CIRCULATED 120 SACKS OF CEMENT TO THE SURFACE. OPERATOR TOPPED OFF TOP PLUG (30') ON 7/2/96.

REMARKS: 60/40 POZ 4% GEL ALLIED #3025

I DIDNOT OBSERVE THIS PLUGGING.

Michael R. Wilson
MICHAEL R. WILSON

INVOICED

DATE 8-16-96

INV. NO. 46274

6-13