

5-10-88

2 100359

API NUMBER 15- 191-20,787 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 12, T 32 S, R 4 WXB

1320 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

RCUP
05-17-88

Operator License # 5822

Lease Name Bruce Well # 2

Operator: Gressel Corp
Name & Address: Box 322
Haysville, KS 67060
316-773-1247

County Sumner 113.10

Well Total Depth 3480 PB 2460 feet

~~CORROSION~~ Pipe: Size 5-1/2 feet 2754

Surface Casing: Size 8-5/8 feet 244

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Perf 1880-84

Plugging Contractor Gressel Corp License Number _____

Address Haysville, KS 67060

Company to plug at: Hour: 8:00a Day: 6 Month: 5 Year: 19 88

Plugging proposal received from Kenny

(company name) Gressel Corp. (phone) 316-773-1247

work: Pump 50 sx of cement on bottom to 1800' - mud to 350' - build bridge and redi mix to surface.

Plugging Proposal Received by Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00p Day: 10 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT Pump cement from 1884 to 1400' - shot and pulled 950' of 5-1/2 pipe - mud to 300' build rock bridge - redi mix to surface with 5 sx cement.

Remarks: Wellington Redimix #60019
(If additional description is necessary, use BACK of this form.)

INVOICE D
Invoice no. _____ serve this plugging.

DATE 8-16-88
INV. NO. 21853 WK

Signed Johnny Sanders (TECHNICIAN)