

9-12

2-040644

198
12

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-191-20,226 0000

C NW NW, SECTION 25 TOWNSHIP 32 RANGE 4W

OPERATOR LICENSE # 7234 4620 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR Arrowhead Petro of KS
NAME & Box 293 - RR #1
ADDRESS Wellington, KS 67152

LEASE NAME: McCall #1
COUNTY: Summner
WELL TOTAL DEPTH: 4337' 18395'

140.95

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 254'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Lyons Well Service
ADDRESS: Lyons, KS LICENSE: 30375

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Willis Lowe
COMPANY NAME: Arrowhead Petro of Kansas, Inc. PHONE: _____

WERE: 5-1/2" @ 4060'/70 sx - perfs MISS 3957-67' - KC 3381-85' - PBSD 3915' - sand to 3900' & 5 sx - sand to 3330' & 5 sx - 35 sx @ 900' - 35 sx @ 600' - circ 300'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 14:30 DAY: 12 MONTH: 9 YEAR: 1991

ACTUAL PLUGGING REPORT:

Csg sanded back to 3900' & capped w/5 sx cmt - bridge pushed below top perfs & covered w/sand to 3330' & capped w/5 sx cmt - 5-1/2" recovered from 1202' & pulled to 909' & 35 sx cmt - pipe pulled to 614' & 35 sx cmt - pipe pulled to 323' & cmt circ to surf.

REMARKS: United #3041 40/60 poz 4% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 11-8-91

INV. NO. 33639

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

9-12 NOV 20 1991

DW