

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-121-02368-0000
 Spot: W2NW Sec 31 Twp 16 S Rng 24 ☒ E / ☐ W
~~4468~~ 4468 Feet from ☐ N / ☒ S Line of Section
5730 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 38.618860 Long: 94.807720 Date: 4/23/09
 Lease Name: BOUSE (GARDNER) Well #: GRD 02
 County: Miami Total Vertical Depth: 460 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>5.500</u>	<u>200</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>460</u>	<u>0</u>	
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: OG - Oil & Gas (Oil) UIC Docket No.: _____ Date/Time to Plug: 6/10/11 / 1:00 pm
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: JEFF FREDRICKS Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

WASH 1" DOWN INSIDE 2" AND OUTSIDE 2". PUMP PORTLAND CEMENT FROM TD TO SURFACE.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 6/10/11 / 3:30 pm KCC Agent: FRANK GUILFOYLE
 Actual Plugging Report: _____ Perfs: _____ Top _____ Bottom _____ Thru _____

RUN 3/4" TO 260 FT OUTSIDE 2". RUN 1" TO 450 INSIDE 2". WASH INSIDE TO 460 FT. WASH OUTSIDE TO 350 FT. PUMP PORTLAND CEMENT FROM TD TO SURFACE INSIDE 2" AND OUTSIDE 2". PULL PIPE AND TOP OFF WELL. EMPTY PIT. DIG DOWN AND CUT OFF SURFACE AND 2". BACKFILL PIT AND LEVEL AREA. PUMP TOTAL OF 83 SACKS OF CEMENT. WELL PLUGGED.

KANSAS CORPORATION COMMISSION
 JUL 01 2011
 RECEIVED

Remarks: CONTROL NUMBER 20110067-002. PURCHASE ORDER 14300-0000000666. IRREG. SECTION.
NAD83

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Frank Guilfoyle
 (Technician)

Form: District Plugging Report - _____