

District Plugging Report

API Well Number: 15-121-02369-0000

Spot: W2NW Sec 31 Twp 16 S Rng 24 ☒ E / ☐ W

4077 Feet from ☐ N / ☒ S Line of Section

5143 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 38.617790 Long: 94.805670 Date: 4/23/09

Lease Name: BOUSE (GARDNER) Well #: GRD 04

County: Miami Total Vertical Depth: 260 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>DRIVE - Drive Pipe</u>	<u>12.000</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>					
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> -					

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 7/1/11 / 10:00 am
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: JEFF FREDRICKS Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report:

CLEAR TREES TO LOCATION. WASH AND OR DRILL TO TD. PLUG WELL

JUL 28 2011
RECEIVED

Plugging Proposal Received By: FRANK GUILFOYLE **Witness Type:** PART - Partial
Date/Time Plugging Completed: 7/1/11 / 12:30 pm **KCC Agent:** FRANK GUILFOYLE
Actual Plugging Report: **Perfs:** **Top** **Bottom** **Thru**

CLEAR TREES TO LOCATION. TRY TO WASH 1". GOT TO 65 FT. HIT WOOD. MOVE DRILL RIG TO LOCATION. DRILL THROUGH WOOD AND ROCK TO 225 FT. PULL DRILL PIPE AND MOVE RIG. PULLING UNIT AND RUN 1" TO 250 FT. WASH TO 260 FT. PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 138 SACKS OF CEMENT. EMPTY PIT AND BACK-FILL. DIG DOWN AND CUT OFF WELL. LEVEL AREA. WELL PLUGGED.

[illegible]

Remarks	PURCHASE ORDER 14300-0000000666. CONTROL # 20110067-003 IRREG. SEC. NAD83
---------	--

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

Frank Smith
(Technician)
Form: District Plugging Report -