

To: 1 031278
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-5

API NUMBER 15- 101-21,672-0000
SE SE SW, SEC. 5, T 19 S, R 29
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

Lease Name Ehmke Well # 1-5

Operator: Ensign Operating Co.

County Lane

Name & Address P.O. Box 2161

Well Total Depth 4665 151.61 feet

Liberal, KS 67905-2161

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 11:30 p.m. Day: 4 Month: 6 Year: 19 94

Plugging proposal received from Rich Wheeler

(company name) Duke Drilling Co. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2167-2185'

1st plug at 2160' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 870' with 40 sx cement, 4th plug at 240' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 a.m. Day: 5 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 870' with 40 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK (Conservation Division Wichita, Kansas))

INVOICED

DATE 6-20-94

INV. NO. 40580

6-5

Signed Steve Durrant (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

JUN 09 1994

6-9-94

CONSERVATION DIVISION Wichita, Kansas