

4-29

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-20,435-00-00

SW SW NW, SECTION 14 TOWNSHIP 22 RANGE 8W

OPERATOR LICENSE # 9132
OPERATOR MILTON LACKEY
NAME & 382 FIRST AVENUE
ADDRESS INMAN, KS 67546

2976 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

LEASE NAME: JUSTUS #B-1
COUNTY: RENO 119.44
WELL TOTAL DEPTH: 3675'
PIPE: 4 1/2" @ 3675'
SURFACE CASING: 8 5/8" @ 250'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 29 MONTH: 4 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MILTON LACKEY

COMPANY NAME: MILTON LACKEY PHONE: (316) 585-2119

WERE: SAND TO 3440' AND 4 SACKS
35 SACKS AT 1150'
35 SACKS AT 650'
300' TO 0'

RECEIVED
KANSAS CORPORATION COMMISSION
5-6-97
MAY 06 1997

PLUGGING PROPOSAL RECEIVED BY: JERRY CLARK

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X) WICHITA, KS

COMPLETED: HOUR: 3:30 DAY: 29 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3440' AND 4 SACKS RAN. SHOT IN TO 2600', WOULDN'T GO OFF. STARTED OUT OF HOLE WITH SHOT WENT OFF AT 600'. PULLED CASING OUT. RAN TUBING IN TO 1150', PUMPED 35 SACKS. PULLED TO 600', PUMPED 35 SACKS. PULLED TO 300', PUMPED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL UNITED #4439

INVOICED
DATE MAY 07 1997
WV. NO. 48083
4-29

I DID NOT OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI