

RECEIVED

3-9

2-

KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

APR 01 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-191-21,052 - 21502-6001

C NW SW, SECTION 16 TOWNSHIP 34 RANGE 4W

OPERATOR LICENSE # 6785 1980 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR SCHULEIN COMPANY
NAME & 1776 LINCOLN ST #811
ADDRESS DENVER CO 80203

LEASE NAME: KOLARIK #1
COUNTY: SUMNER
WELL TOTAL DEPTH: 4876' 158.47

PIPE: 4-1/2" @ 4842'
SURFACE CASING: 8-5/8" @ 298'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD DEA

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YEAR: 1994

PLUGGING PROPOSAL RECEIVED FROM: CARL DURR

COMPANY NAME: FIELD OPERATION INC PHONE: _____

WELL: PERFS 4456'-66' - 4526'-40' - CIBP 4610' - SAND BACK
& 4 SX - 35 SX @ 850' - 35 SX @ 600' - CIRC 350' TO 0'

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 9 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:

CIBP SET @ 4400' & CAPPED W/2 SX CMT - 4-1/2" CSG SHOT
OFF @ 3370' & PULLED TO 870' & 35 SX CMT SPOTTED -
4-1/2" CSG PULLED TO 584' & 35 SX CMT SPOTTED - 4-1/2"
PULLED TO 378' & CMT CIRC TO SURF - REMAINING 4-1/2"
CSG PULLED FROM WELLBORE & THE CMT FILLED BACK TO SURF

REMARKS: ALLIED #4717 60/40 4% GEL

INVOICED

DATE APR 01 1994

13/
STEVE VAN GIESON (AGENT)

INV. NO. 40207