

Tg  
1 090379  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,282-0000  
C NW SE, SEC. 12, T 19 S, R 29 W/E  
1980 feet from S section line  
1980 feet from E section line  
Lease Name Thomas "A" Well # 2  
County Lane  
Well Total Depth 4674 151.91 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 230

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5393  
Operator: A.L. Abercrombie, Inc.  
Name & Address Rt. 1, Box 56  
Great Bend, KS 67530

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 20 Month: 12 Year: 1993  
Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943  
wells: 5 1/2" at 4672' w/150 sx cement, PBSD 4515', Perfs at 4080-85, 4367-72'

1st plug sand back to 4030' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 80 sx cement at 1250',  
3rd plug pump 40 sx cement at 600', 4th plug pump 50 sx cement at 360',  
5th plug pump 10 sx cement at 40'.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1993  
12-23-93  
CONSERVATION DIVISION  
Wichita, Kansas  
Steven Middleton  
(TECHNICIAN)

Plugging Proposal Received by

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:15 p.m. Day: 20 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4030' and dumped 5 sx cement on top of sand through bailer,

2nd plug shot casing at 2100', could not pull. Spotted cement bridge between 1250 and 2100'.  
Shot casing at 1250' and spotted 80 sx cement,

3rd plug shot casing at 800' and pulled to 260', circulated cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 800' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If you wish to observe this plugging.

DATE DEC 29 1993  
INV. NO. 39566  
12-20

Signed *[Signature]*  
(TECHNICIAN)