

To: 1 050002
STAT CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-101-20,489 -0000
C SW, SEC. 10, T 19 S, R 29 W/EX
1320 feet from S section line
3960 feet from E section line

12-18
TECHNICIAN'S PLUGGING REPORT
Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name:
Address Rt. 1, Box 56
Great Bend, KS 67530

Lease Name McWhirter Well # 2
County Lane 151.58
Well Total Depth 4664 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 10 a.m. Day: 18 Month: 12 Year: 1996

Plugging proposal received from James Ray
(company name) Mike's Testing & Salvage, Inc. (phone) 316-793-8186

were: 4 1/2" at 4658' w/250 sx cement, PBTD 4633', Perfs at 4428-32, 4268-71'
1st plug pump 1 sx hulls and 25 sx cement, displace to 4400',
2nd plug perforate at 1300' and pump 80 sx cement over capacity of pipe,
3rd plug pump 150 sx cement down 8 5/8" X 4 1/2".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12:45 p.m. Day: 18 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped 100 sx cement at 1250',
3rd plug pumped 40 sx cement at 520',
4th plug pumped 50 sx cement at 260',
5th plug pumped 10 sx cement at 40'.
12-23-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (K. D. [unclear]) reserve this plugging.

Signed Michael J. Mann
(TECHNICIAN)

INVOICED
DATE DEC 31 1996
INV. NO. 47193
12-18