

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-121-02447-0001
Spot: NENESW Sec 25 Twp 16 S Rng 23
Feet from 2475 N / S Line of Section
Feet from 2807 E / W Line of Section
GPS: Lat: 38.627960 Long: 94.818110 Date: 1/30/12
Lease Name: Marion Butts (Reinpart) Well #: BUT 02
County: Miami Total Vertical Depth: 525 feet

Operator License No: 101
Op Name: STATE OF KANSAS
Address 1: 130 S. MARKET
Address 2:
City: WICHITA
State: KS Zip Code: 67202

Well Type: OG - Oil & Gas
Plug Co License No.: 33749
Proposal Rcvd from: Mike Kepley
UIC Docket No.:
Date/Time to Plug: 8/24/12
Plug Co. Name: KEPLEY WELL SERVICE, LLC.
Company Name: KWS Phone: (620) 431-8945

Proposed Plugging Report:

Pump portland cement from TD to surface.

Plugging Proposal Received By: Frank Guilfoyle
Date/Time Plugging Completed: 8/24/12
Witness Type: COMP - Complete 100%
KCC Agent: FRANK GUILFOYLE

Actual Plugging Report table with columns: Perfs, Top, Bottom, Thru. Includes text: This well was drilled as an Oil/Gas well and declared a dry hole. Then it was plugged back and saved as a water well. It was plugged at 120 ft with a wood and rock bridge and 3 sacks of cement. Wash 1" to 100 ft and hit hard. Could not get any deeper. Move in drill rig and start drilling at 100 ft. Drilled through cement, rocks, and wood and ran drill pipe to 200 ft without hitting anything else. Pull drill pipe and move rig off well. Run 1" and wash to 525 ft and hit hard. Pump portland cement from TD to surface. Pull pipe and top off well. Pump total of 159 sacks of cement. Well plugged.

KANSAS CORPORATION COMMISSION
OCT 02 2012
RECEIVED

Remarks: Contract number 11782. Control number 20120045-002. Reg. Sec. NAD 83.

Plugged Thru: TBG - Tubing
Plugged Due to Compliance Issue: Yes No

District: 03
Signature: Frank Guilfoyle
(Technician)
Form: District Plugging Report