

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20325-0000 R  
NE NW Sec. 11, T 19 S, R 29 W/E  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Ahnert "A" Well # 1

Operator: Donald C. Slawson  
Name & Address 200 Douglas Building  
Wichita, KS. 67202

County Lane

Well Total Depth 4650' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 261' w/175 SX

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050 priv tag 547

Address Box 176 Chase, KS. 67524

Company to plug at: Hour: 11:30 Day: 16 Month: Feb Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso Casing Pulling (phone) \_\_\_\_\_

were: 50/50 poz mix 4% gel 3% cc

1st plug 4200' sand to 4200' + 4 sx cement

2nd plug 3 hulls - 10 gel - 70 sx cement - 20 gel -

1 hulls - 1 wiper plug - 130 sx cement

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 16 Month: Feb Year: 1983

ACTUAL PLUGGING REPORT 50/50 poz mix 4% gel 3% cc

1st plug Sand to 4200' + 4 sx cement

2nd plug 3 hulls - 10 gel - 70 sx cement - 5 gel

1 hulls - 1 wiper plug - 130 sx cement

Max. Pump Pressure 1100 psi Shut in Pressure 200 psi

Recovered 2500' of 4 1/2" production casing

Remarks: Steve Durrant Gave Orders

Perforations at 4211' to 4212" 4270" - 72"

4649' of 4 1/2" cemented w/175 SX

Plugged Back TD 4312. Haliburton did the cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

STATE CORPORATION COMMISSION  
RECEIVED  
FEB 22 1983  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE MAR 24 1983  
INV. NO. 36704