

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20330-0000

R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

200' E of NWNW Sec. 11, T 19 S, R 29 W & E
_____ feet from N/S section line
_____ feet from W/E section line

Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

Lease Name Ahnert "A" Well #2
County Lane
Well Total Depth 4675 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 270 W/175 SX

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso casing Pulling License Number 6050 rig tag 547
Address Box 176 Chase Kansas 67524

Company to plug at: Hour: 2:30 pm Day: 16 Month: Feb Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh
(company name) Kelso Casing Pulling (phone) _____

were: 50/50 pozmix 4% gel 3% cc

1st Plug ~~1~~ Sand back to 4250 + 4 SX cement

2nd Plug 3 holls - 10 gel - 70 SX cement - 20 gel

1 holl - 1 wiper plug - 130 SX Cement

Perfs 4310-4313 4489-4493

PBTD 4633 Signed Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 pm Day: 16 Month: Feb Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph

Max. pumping pressure 800 psi

Shut in pressure 200 psi

Recovered 2520' of 4 1/2 production casing

Haliburton did the cementing

Remarks: Steve Durrant gave Plugging orders

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

Signed Richard W. Lacy
(TECHNICIAN)

INVOICED

FEB 22 1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82

DATE MAR 24 1983

INV. NO. 3668-6