

1020186

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SW SE, SEC. 11, T 19 S, R 29
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,113-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Operator: Chief Drilling Co., Inc.

Name &

Address 905 Century Plaza

Wichita, KS 67202

990 feet from N/S section line

1650 feet from N/E section line

Lease Name Paris "A" Well # 1

County Lane 151.45

Well Total Depth 4660 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. Rig 2 License Number 5886

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 28 Month: January Year: 19 85

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2140' with 50 sx cement

2nd plug at 1320' with 60 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:15 am Day: 28 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2140' with 50 sx cement, 2nd plug at 1320' with 60
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to
circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(additional description is necessary, use BACK of this form.)

I () / did not observe this plugging.

DATE 2-6-85

INV. NO. 6838

Signed

(TECHNICIAN)