

To: 1090289 6-2  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,650-0000  
SE NE SE, SEC. 11, T. 19 S, R. 29 W/E  
1650 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30269  
Operator: Argent Energy, Inc.  
Name: Argent Energy, Inc.  
Address 110 S. Main, Ste. 810  
Wichita, KS 67202

Lease Name Paris Well # 1  
County Lane  
Well Total Depth 4648 151.06 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039  
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 2 Month: 6 Year: 19 93  
Plugging proposal received from Bessie  
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2163'  
1st plug at 2170' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,  
3rd plug at 670' with 40 sx cement, 4th plug at 240' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 3:30 p.m. Day: 2 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2170' with 50 sx cement,  
2nd plug at 1350' with 80 sx cement,  
3rd plug at 670' with 40 sx cement,  
4th plug at 240' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floeal by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I did not observe this plugging.  
DATE 6-14-93  
INV. NO. 37891

RECEIVED  
JUN 4 1993  
Signed Steve Middleton  
(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas