

3021121

9-27

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 WICHITA STATE OFFICE BLDG., 130 S. MARKET
 WICHITA, KANSAS 67202
 TECHNICIAN'S PLUGGING REPORT
 OPERATOR LICENSE # 31401
 OPERATOR: MOVALCO HOLDING, INC.
 NAME AND ADDRESS 5225 W. 75TH, BOX 8357
PRAIRIE VILLAGE, KS 66208

API NUMBER 15- ~~207-24,420~~ 24470-0000
 NW, SEC. 34, T 25 S, R 15 E
3500 FEET FROM SOUTH SECTION LINE
3980 FEET FROM EAST SECTION LINE
 LEASE NAME EAST EGGERS WELL # I-7
 COUNTY WOODSON
 WELL TOTAL DEPTH 1219 39.62 FEET
 CONDUCTOR PIPE: SIZE _____ FEET _____
 SURFACE CASING: SIZE 5 1/8 FEET 40
 ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL E-21,926SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____
 PLUGGING CONTRACTOR HAROLD CORBETT LICENSE NUMBER 31505
 ADDRESS ROUTE 2, BOX 198, CHERRYVALE, KS 67335

COMPANY TO PLUG AT: HOUR: 4:45 PM DAY: 27 MONTH: 9 YEAR: 95
 PLUGGING PROPOSAL RECEIVED FROM RICK WARD
 (COMPANY NAME) MOVALCO HOLDING, INC. (PHONE) 316-431-0704

WERE: THIS WELL CONSISTED OF 2 1/2" CASING TO 1210' THAT HAD BEEN CEMENTED IN FROM
BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 1/2" CASING FULL OF CEMENT
FROM SURFACE.

PLUGGING PROPOSAL RECEIVED BY C. TITEL
 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 5:20 PM DAY: 27 MONTH: 9 YEAR: 95

ACTUAL PLUGGING REPORT THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 1/2" CASING
COTTONSEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS
PUMPED INTO THE 2 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. STATE CORPORATION COMMISSION
SHUT-IN. AN ESTIMATED 25 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
 OCT 19 1995
 10-19-95
 CONSERVATION DIVISION
 Wichita, Kansas

REMARKS: _____
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel
 (TECHNICIAN) FORM CP-2/3

INVOICED
 DATE 10-31-95
 BILL NO. 43912
 9-27 DEC 11 1995