

4040646

5-2

14
R

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202
 TECHNICIAN'S PLUGGING REPORT
 OPERATOR LICENSE # 5721
 OPERATOR: GLACIER PETROLEUM INC.
 NAME AND ADDRESS 825 COMMERCIAL STREET., BOX 577
EMPORIA, KANSAS 66801

API NUMBER 15- 197-20,236 ~~0000~~
NE, SEC. 29, T 14 S, R 10 E
4950 FEET FROM SOUTH SECTION LINE
330 FEET FROM EAST SECTION LINE
 LEASE NAME W. ASHBURN WELL # 1
 COUNTY WABAUNSEE 110.01
 WELL TOTAL DEPTH 3385 FEET
 CONDUCTOR PIPE: SIZE _____ FEET _____
 SURFACE CASING: SIZE 8 5/8 FEET 301

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A X
 OTHER WELL AS HEREINAFTER INDICATED _____
 PLUGGING CONTRACTOR WHITE & ELLIS LICENSE NUMBER 5420
 ADDRESS 401 E. DOUGLAS, SUITE 500, WICHITA, KANSAS 67202

COMPANY TO PLUG AT: HOUR: 2:00 AM DAY: 2 MONTH: 5 YEAR: 91
 PLUGGING PROPOSAL RECEIVED FROM VERNON GLAZE
 (COMPANY NAME) WHITE & ELLIS DRILLING (PHONE) 316-263-1102
 WERE: 125 SACKS FROM TD-3385' TO 3000'. COVERS SIMPSON UP TO TOP OF HUNTON. 25 SACKS AT TOP OF KC
AT 2400'. 30 SACKS AT 325' TO 235'. DRILL MUD TO 60', 25 SACKS FROM 25' TO SURFACE. 10 SACKS IN RATHOLE.

PLUGGING PROPOSAL RECEIVED BY LEON WINTERS
 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X
 OPERATIONS COMPLETED: HOUR: 5:00 AM DAY: 2 MONTH: 5 YEAR: 91
 ACTUAL PLUGGING REPORT PUMPED 125 SACKS FROM 3385' TO 3000'. PULLED DRILL PIPE TO 2400' AND PUMPED 25
SACKS AT TOP OF KC. PULLED DRILL PIPE TO 325' AND PUMPED 30 SACKS TO 235'. FILLED SURFACE PIPE TO 60'
WITH DRILL MUD. CEMENT TOP 60' WITH 25 SACKS CEMENT. 10 SACKS CEMENT IN RATHOLE. 215 SACKS. 42 VISC. 14#.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 06 1991
 CONSERVATION DIVISION
 Wichita, Kansas

REMARKS: HAD BAD LOSS CIRC. IN HUNTON.
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (XXX/DID NOT) OBSERVE THIS PLUGGING.

SIGNED Leon Winters
 (TECHNICIAN)

FORM CP-2/3

INVOICED

DATE 6-10-91
 INV. NO. 32046