

2 050376

API NUMBER 15- 191-20,877 0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NE SW, SEC. 19, T 33 S, R 3 W/EX

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Operator License # 5046

Lease Name Stewart Well # 1

Operator: Raymond Oil Company  
Name & Address P.O. Box 48788  
Wichita, KS 67201

County Sumner 147.55

Well Total Depth 4540 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number 6050

Address Chase, KS

Company to plug at: Hour: 8 a.m. Day: 24 Month: 4 Year: 19 86

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 5 1/2" casing set at 4534 feet - perf at 4490-4497' sand back to 4450 feet and dump  
6 sacks of cement - shoot and pull pipe - squeezed 8 5/8" with 15 sacks of gel,  
3 sacks of hulls, 100 sacks of 60/40, 4% gel

Plugging Proposal Received by Warren Kirkpatrick  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 25 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Sanded back to 4450 feet and dumped 6 sacks of cement with dump  
bailer. Shot and pulled 3800 feet of 5 1/2" casing. Squeezed 8 5/8" with 15 sacks  
of gel, 3 sacks of hulls, and 100 sacks of 60/40 pos, with 6% gel.

Closed in at 350#

Remarks: United 9623  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
MAY 15 1986  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

DATE MAY 15 1986  
INV. NO. 13839

*W*

Signed Glenn J. Ward  
(TECHNICIAN)

RO