

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20877-00-00
Spot: E2NWNWSE Sec/Twnshp/Rge: 23-24S-13W
2357 feet from S Section Line, 2214 feet from E Section Line
Lease Name: MORGAN Well #: 1
County: STAFFORD Total Vertical Depth: 3004 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1707		WITH 2 SX CMT
PROD 4.5		1959	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/11/2013 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 1700' & 2 SX CMT. PERFORATE @ 760'. PUMP DOWN 4 1/2" WITH CMT. CIRCULATE CMT UP 8 5/8".

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2013 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 1707'. PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 4 1/2" CASING @ 760'. PUMPED DOWN 4 1/2" CASING WITH 240 SX CMT. CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS. CUT PIPE OFF & TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1800	1800		

RECEIVED
JAN 24 2013
KCC WICHITA

Remarks: CONTROL# 20130056-001 USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

JAN 17 2013

KCC DODGE CITY

