

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21779-00-00
Spot: NESE Sec/Twnshp/Rge: 25-28S-15W
1982 feet from S Section Line, 684 feet from E Section Line
Lease Name: JOHNSON E Well #: 1A
County: PRATT Total Vertical Depth: 4750 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4713	1935	WITH 150 SX CMT
SURF	8.625	301		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2013 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4500' & 4 SX CMT. PLUG AT 940' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/15/2013 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SANDED TO 4468' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 943' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
JAN 24 2013
KCC WICHITA

Remarks: CONTROL # 20130034-001 USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JAN 17 2013
KCC DODGE CITY

PAW