

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20781-00-00
Spot: NENENW Sec/Twnshp/Rge: 33-25S-16W
4907 feet from S Section Line, 2975 feet from E Section Line
Lease Name: ROENBAUGH Well #: 1
County: EDWARDS Total Vertical Depth: 4578 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4477	1820	WITH 200 SX CMT
SURF	8.625	329		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2013 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4200' & 4 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 01/22/2013 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

TBG & RODS WERE HUNG UP IN HOLE. GOT RODS LOOSE & LAID DOWN RODS & PUMP. SHOT OFF TBG & LAID DOWN 3914' OF 2 3/8" TBG. SET WOOD PLUG ON TOP OF TBG FISH & SANDED BACK TO 3860'. PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT.

RECEIVED
JAN 31 2013
KCC WICHITA

Remarks: CONTROL # 20120068-001. USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
JAN 23 2013
KCC DODGE CITY

HWY