

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-007-26206-0000
 Spot: S2SE Sec 12 Twp 24 S Rng 15 E / W
215 Feet from N / S Line of Section
2197 Feet from E / W Line of Section
 GPS: Lat: 37.966830 Long: 95.709880 Date: 6/21/10
 Lease Name: STURDIVAN (WESTON) Well #: STU 01
 County: Woodson Total Vertical Depth: 1080 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>COND - Conductor Pipe</u>	<u>6.000</u>	<u>40</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>PROD - Casing</u>	<u>2.500</u>	<u>1.080</u>	<u>0</u>	
Address 2: _____	<u>PKR - Packer</u>	<u>1.000</u>	<u>25</u>	<u>25</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u>					

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 5/3/11 / 10:00 am
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: MIKE KEPLEY Company Name: SAME Phone: (620) 431-8945

Proposed Plugging Report: **PULL PACKER AND 1" FROM WELL. PUMP PORTLAND CEMENT FROM TD TO SURFACE.**

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: ZERO - None
 Date/Time Plugging Completed: 5/3/11 / 11:30 am KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
<p>PULL 1" AND PACKER. RUN 1" AND REAMER TO 500 FT. PULL OUT AND PERFORATE AT 500 AND 300 FT. RUN 1" TO TD. PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL 1" AND TOP OFF WELL. DIG OUT WELL AND CUT OFF BELOW GROUND. EMPTY PIT AND FILL IN. LEVEL AREA. WELL PLUGGED. PUMP TOTAL OF 54 SACKS OF CEMENT.</p>		<u>100</u>	<u>300</u>	<u>CSG - Casing</u>

KANSAS CORPORATION COMMISSION
 MAY 20 2011
 RECEIVED

Remarks: **CONTROL # 20110024-001. PURCHASE ORDER # 14300-0000000172. REG. SEC.**

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03

 (Technician)
 Form: District Plugging Report - _____