


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Harper _____ County, Sec. 36 Twp. 31S Rge. 7 (E) W (W)
Location as "NE/CNW*SW*" or footage from lines SE SE
Lease Owner KATHOL PETROLEUM, INC.
Lease Name Haskins Well No. 2
Office Address 900 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/24/68 19____
Application for plugging filed 12/18/68 19____
Application for plugging approved 12/23/68 19____
Plugging commenced 1/1/69 19____
Plugging completed 1/1/69 19____
Reason for abandonment of well or producing formation Sturcture not prod-
uctive for Commerical use.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? _____

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4348 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	238'	None
				5-1/2	4336'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pull 13 jts. pipe - total 2200 ft - mud to 225 ft. - 10 ft. rock bridge to 215 - dump 3 1/2 yds ready mix cement to surface .

RECEIVED
STATE CORPORATION COMMISSION
2-11-69
FEB 11 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KATHOL PETROLEUM, INC.
Address 900 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Homer J. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer J. Catt
900 Sutton Pl., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 10th day of February, 19 69
Dixie Lee Brown
Dixie Lee Brown Notary Public.
My commission expires June 17, 1972



KATHOL PETROLEUM, INC.

DRILLERS LOG

No. 2 HASKIN

C SE SE Section 36-31S-7W

Harper County, Kansas

Commenced: 11-16-68 U.S.
 Completed: 11-24-68 R.T.D.
 Elevation: 1426' KB

FROM	TO	FORMATION	REMARKS
238	920	Redbed & clay	Ran 6 jts, 20# new, 8-5/8" surface casing, cemented at 238' w/200 sx 1% gel & 2% calcium chloride.
920	1435	Shale & shells	
1435	1622	Shale & lime	
1622	1825	Lime	
1825	2030	Lime & Shale	
2030	2130	Shale & lime	
2130	2465	Shale	
2465	2700	Shale & lime	
2700	2910	Shale & lime stks.	
2910	3140	Shale & lime	
3140	3300	Shale & lime	
3300	3550	Shale	
3530	3750	Shale & lime	
3750	3815	Shale & lime	
3815	3869	Lime	
3869	3975	Lime	LOG TOPS: Kansas Ctiy 3742' (-2316) Base/K.C. 3960' (-2534) Marmaton 4034' (-2612) Cherokee 4160' (-2734) Mississippi 4334' (-2908) R.T.D. 4343' (-2917)
3975	4069	Shale & lime	
4069	4320	Shale & lime	
4320	4348	Lime & chert	
4343		R.T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 2-11-69
 FEB 11 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate drillers log record of the captioned well.

Don Shawver
 Don Shawver

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss

Subscribed and sworn to before me this 13th day of December, 1968.

Betty M. Maloney
 Betty M. Maloney, Notary Public

