


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sumner County. Sec. 1 Twp. 33 Rge. (E)-2 (W)
Location as "NE/CNW%SW%" or footage from lines NE NE SW
Lease Owner Earl F. Wakefield, et al
Lease Name Blue Well No. 1
Office Address 307 Union Nat'l Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 12 1952
Application for plugging filed " " 1952
Application for plugging approved " " 1952
Plugging commenced " " 1952
Plugging completed " " 1952
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. E. Buffington
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4298 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	126.07	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled with Heavy Mud from 4298' to 135 feet, cemented with 15 sacks cement at 135 feet, filled with mud to 30 feet, cemented to top with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield
Address 307 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl F. Wakefield (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
307 Union Nat'l Bank Bldg.
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1952

My commission expires 12-23-54

Jeanne Gabrey Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC LT 33-R27
BOOK 44 LINE 3

SEP 13 1952
CONSERVATION DIVISION
Wichita, Kansas

Blue #1
 Owner: Earl F. Wakefield et al
 Contractor: Earl F. Wakefield
 Comm: 8/26/52 Comp: 9/12/52

NE NE SW 1-33S-2W
 Sumner County, Kansas
 Casing: 125' of 8 5/8"

Elevation: 1240 D. F.

Surface	125
Shale & Shells	280
Shale & Lime Stks.	660
Shale	670
Sandy Shale	700
Lime & Shale	1210
Shale & Lime Stks.	2765
Shale	1790
Lime	1850
Shale & Shells	1865
Lime & Shale	2150
Shale	2155
Lime	2250
Shale & Lime	2390
Lime	2470
Shale & Shells	2510
Lime & Shale	2775
Shale & Lime Stks.	2900
Shale	2915
Sand-Stalmer	2945
Lime	3000
Shale & Lime	3208
Lime-Kansas City	3480
Lime & Shale	3550
Shale & Lime Stks.	3610
Lime & Shale	3690
Lime Broken	3735
Lime & Shale	3876
Lime-Mississippi	4208
Shale	4295
Sempson Sand	4298
Total Depth	4298

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

I hereby agree and certify that the above is a true and correct copy of the log on the Blue #1 well located NE NE SW 1-33S-2W, Sumner County, Kansas.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 18 1952

CONSERVATION DIVISION
 Wichita, Kansas

Earl F. Wakefield

Subscribed and Sworn to before me this 16th day of September, 1952

E. Jeanne Gaffney

My Commission Expires: 12-23-54

PLUGGING
 FILE SEC 1-T-34-R-2W
 BOOK PAGE 44 LINE 2