


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-191-00817-0000  
Form CP-4

NORTH



Locate well correctly on above  
Section Plat

Sumner County. Sec. 14 Twp. 33S Rge. (E) 2 (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SE  
Lease Owner Pack Oil Co.  
Lease Name Mickley-Watts Unit Well No. 1  
Office Address Box 1198, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 16, 19 63  
Application for plugging filed February 16, 19 63  
Application for plugging approved February 16, 19 63  
Plugging commenced February 16, 19 63  
Plugging completed February 16, 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess  
Producing formation Depth to top Bottom Total Depth of Well 4291 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	228'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud to 250 feet.  
Bridged at 250 feet with hulls & 15 sacks  
cement on bridge. Hole filled with heavy  
rotary mud to 35 feet. Bridge at 35 feet  
with hulls & 8 sacks cement on bridge. Rat  
hole capped with 2 sacks cement.

FEB 25 1963

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc. License #209  
Address Box 448, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Ernest Sifford, employee of Contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford  
Box 448, El Dorado, Kansas  
(Address)

Subscribed and Sworn to before me this 25th day of February, 19 63

My Commission expires September 26, 1964

L. B. Auer

Notary Public.

# Boring Record

8 5/8

228' Cemented  
w/180 sacks

T. D.

4291'

Kelly Bushing Measurement 5' above ground level.

FORMATION	DEPTH
Clay & Shale	0-34
Sand & Shale	50
Shale, Lime & Sand	80
Shale & Lime stks.	217
Shale	400
Lime	450
Shale & Lime stks.	550
Lime	800
Lime & Shale	930
Lime	1190
Lime & Shale	1515
Shale & Lime	2390
Lime & Shale	2775
Shale	2868
Lime & Shale	3096
Shale	3251
Lime	3520
Shale & Lime stks.	3572
Lime	3655
Lime & Shale	3785
Shale	3880
Shale & Lime	3912
Lime	4220
Shale	4287
Sand	4291

## TOPS

Stalnaker	2868
Kansas City	3251
Mississippi	3912
Simpson	4287

15 - 191 . 00817 0000  
Location: SW SW SE  
Section: 14-33S-2W  
Sumner County, Kansas  
Farm: Mickley #1 - Watts Unit  
Well Owner: Pack Oil Co.  
Contractor: White & Ellis Drig., Inc.  
Started: 1/31/63  
Completed: 2/16/63

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 17 1963

CONSERVATION DIVISION  
Wichita, Kansas

Dry Hole - Plugged & Abandoned