

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
1 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-077-00945-00-01

LEASE NAME Sanders

WELL NUMBER 2

1650 Ft. from N Section Line

2310 Ft. from W Section Line

SEC. 6 TWP. 31S RGE. 8W (E) or (W)

COUNTY Harper

Date Well Completed 9-1-1958

Plugging Commenced 6-13-02

Plugging Completed 6-18-02

LEASE OPERATOR MULL DRILLING CO., INC.

ADDRESS P.O. Box 2785 Wichita, Kansas 67201

PHONE (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 4-16-02 (date)

Steve VanGieson (KCC District Agent's Name).

ACO-1 filed? Yes (use) If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian (use) Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4480

Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	224'	None
				5-1/2"	4480'	2620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Pumped bottom with 50 sacks cement and 150# hulls, displaced with 99 bbls. water. Shot pipe 3220, 2800 & 2620'. Pulled up to 1450' and pumped 35 sacks cement, pulled up to 975', pumped 35 sacks cement, pulled up to 275' and circulated 90 sacks cement to surface. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of July, 2002

NOTARY PUBLIC - State of Kansas  
IRENE HEBZBERG  
My Appt. Exp. 8-24-05

My Commission Expires: