

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-00005-00-00
Spot: NWNW Sec/Twnshp/Rge: 10-35S-21W
4654 feet from S Section Line, 4877 feet from E Section Line
Lease Name: TUTTLE C H - C Well #: 1
County: CLARK Total Vertical Depth: 5575 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	5718	2004	WITH 525 SX CMT
SURF	8.625	675		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/18/2013 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8881

Proposed Plugging Method: CIBP @ 5575' & 2 SX CMT. PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 03/18/2013 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

TBG WAS CUT AT TOP OF HUNG UP ANCHOR CATCHER. PUMPED DOWN TBG @ 5300' WITH 35 SX COMMON CMT & 200# HULLS. 1ST PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5625	5638	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONTROL # 20130055-001 USED 60/40 POZMIX 4% GEL QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
MAR 22 2013
KCC DODGE CITY

Handwritten initials