

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-00945-00-01  
Spot: NESENW Sec/Twnshp/Rge: 6-31S-8W  
1650 feet from N Section Line, 2310 feet from W Section Line  
Lease/Unit Name: SANDERS Well Number: 2  
County: HARPER Total Vertical Depth: 4480 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: PO BOX 2758 221 N MAIN STE 300  
WICHITA, KS 67201

Conductor Pipe: Size feet: 8/45.60  
Surface Casing: Size 8.625 feet: 224 135 SX CMT  
Production: Size 5.5 feet: 4480 100 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/17/2002 6:45 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: NANCY STINER Company: MULL DRILLING Phone: (316) 264-6366

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 06/17/2002 6:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Pumped a 50sxs plug to 3960'. Set overnite. Shot pipe at 3200', couldn't pull, shot pipe at 2620' and pulled to 1450'. Spotted 35sxs cement. Pulled pipe to 975'. Spotted 35sxs cement pulled pipe to 275' and circulated cement to surface. Pull pipe and topped off cement.

RECEIVED  
KCC DISTRICT #2


JUN 24 2002  
6-24-02  
WICHITA, KS

Remarks: ALLIED CEMENT 60/40, 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-25-02  
INV. NO. 2002062009