

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-5

API NUMBER: 15-077-19000-0000

NE-NE-SW SECTION 6 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5123
OPERATOR Pickrell Drilling Co.
NAME 110 S. Market #205
ADDRESS Wichita KS. 67202

2310 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

LEASE NAME: Drake B-3
COUNTY Harper
WELL TOTAL DEPTH: 4525 147.08
PIPE: 5/1/2 @ 4524'
SURFACE CASING 8 5/8 @ 236'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING CONTRACTOR: Clarke Corp.
ADDRESS: Medicine Lodge KS.

LICENSE: 5105

JAN 11 1999

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR:

1-11-99
CORPORATION COMMISSION
WICHITA, KANSAS

PLUGGING PROPOSAL RECEIVED FROM: Jack Gurley
COMPANY NAME: Pickrell Drilling Co. PHONE:
WERE: Sand to 4325' and 5 sacks of Cement
35 Sacks at 1675', 35 Sacks at 975', Circulate Cement from 290'-0'

PLUGGING PROPOSAL RECEIVED BY: Steve VanGieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (x) NONE ()

COMPLETED: HOUR: 1130 DAY: 5 MONTH: / YEAR: 1999

ACTUAL PLUGGING REPORT: The Open Hole was filled with sand to 4325' and capped with 5 sacks of Cement. The Casing was recovered from 2450' and pulled from the wellbore. Tubing was run to 1460' where 35 sacks of cement was spotted. The tubing was pulled to 976' where 35 sacks of cement was spotted. The tubing was pulled to 305' where cement was circulated to surface.

REMARKS: Allied Cementing 60/40 Poz 4% gel

I DID NOT OBSERVE THIS PLUGGING.

Steve VanGieson

1-15-99

60540