

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-28-1995

2- 2040945

API NUMBER: 15-077-01008-0000

NE-NE SECTION 36 TOWNSHIP 31 RANGE 7W

OPERATOR LICENSE # 5429 4620 FEET FROM S SECTION LINE
OPERATOR Bryce F Hayes 660 FEET FROM E SECTION LINE
NAME P.O. Box 108
ADDRESS Attica KS. 67009
LEASE NAME: D.K. Williams
COUNTY Harper
WELL TOTAL DEPTH: 3975 129.19
PIPE: 4 1/2 @ 4003
SURFACE CASING 8 5/8 @ 214

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corp.
ADDRESS: Medicine Lodge KS. LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: _____

PLUGGING PROPOSAL RECEIVED FROM: Alan Viatral
COMPANY NAME: Clark Corp. PHONE: _____
WERE: Cover Perfs with sand and cap with 4 sks. Of cement
35 sks @ 1170
35 sks @ 747
Circ. Cement from 260-0

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: _____

OCT 21 1998


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()
COMPLETED: HOUR: 1600 DAY: 28 MONTH: 12 YEAR: 1995

10-21-98
CONSERVATION DIVISION
WICHITA KS

ACTUAL PLUGGING REPORT: The Perfs. Were covered with sand from 3975-3470, and capped with 4 sacks of cement. The 4 1/2 was recovered from 3316 and pulled from the wellbore. Tubing was run to 1170 where 35 sks. Of cement was spotted. The Tubing was pulled to 747 where 35 sks. Of cement was spotted. The Tubing was pulled to 260 where cement was circulated to surface.

REMARKS: Allied Cementing 60/40 Poz 4 % gel

I DID OBSERVE THIS PLUGGING.


Steve VanGieson

FORM CP-2/3
REV. 3/90

OCT 21 1998

6015!