

15-877-00261-0000

State of Kansas

FORM - CP-2



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

8-31-62
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date August 28, 1962, 1962, authorized
the following plugging operation:

Operator's full Name: Glen T Summar ET AL

Complete Address: 205 Columbia Bldg.. Tulsa, Oklahoma.

Lease Name: Michael C. Seyb. Well No. #1

Location: SW/4 NE/4 Sec. 36 Twp. 31 Rge. 7 (E) (W) X

County Harper Total Depth 4750'

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

229' of 8 5/8" surface pipe circulated with cement. Hole
filled to 200' with heavy drilling mud, 1 sack bulls, 1st
cementing plug and 20 sacks cement through drill pipe.

Hole filled to 35' with heavy drilling mud, 1 sack bulls,
2nd cementing plug and 10 sacks cement to base of cellar.
Rat hole bridged and 2 sacks cement.

Herman J. Suster
Conservation Division Agent