

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name W. D. Start
Complete Address Box 45, Oxford Kans 67119
Lease Name Myers Well No. 1
Location SE 21/4 NE Sec. 2 Twp. 31 Rge. 2 (W)
County Sumner Total Depth 3305
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____
Plugging Contractor B & S Well Service
Address Keyfield Kans. 67156 License No. 685
Operation Completed: Hour 3:15 pm Day 8 Month 11 Year 1974

The above well was plugged as follows: 250' - 10 1/2" - 6" cas. top perf. 3108'
Fill with sand to 3100' & dumped 6
sacks cement with dump trailer. Pulled casing
and pushed plug to 238', put in 10' rock bridge
and 35 sacks cement. Filled with mud to
25' and put in 10 sacks cement which filled
to bottom of collar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eugene Graham
Well Plugging Supervisor

DATE 11/12/74
INV. NO. 7752-E