

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Q

File No. _____ County: Wabaunsee
Location: SE-SE SW Sec. 29 Twp. 14 Rge. 10 (E) (W)
Name of Field: Wildcat Total Depth: 3313

I have this date completed supervision of plugging of:

Lease Name: J Andres Well No. 1
Operator's Full Name: Wm Hrusenewald
Complete Address: 35 E Wacker Drive Chicago Ill
Plugging Contractor: White + Ellis Inc
Address: El Dorado, Ks License No. Ratary
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: *NO*

Operation Completed: Hour 6 AM Day 19 Month Oct Year 1958

The above well was plugged as follows:

Hole full of heavy mud to 240 ft
Plug & dumped 10 sacks of cement
mud to 40 ft plug & dumped 8
sacks of cement to surface
Plug & 2 sacks of cement in
Rat Hole

Signed: *W H Lloyd*
Conservation Division Agent

Reviewed: *Graham*
Field Supervisor

Remarks:

10-27-58
OCT 27 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 14 R 10E
BOOK PAGE 142 LINE 18

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-197-00034-0000
COPYR.

Company- WM. GRUENERWALD
Farm- J. Andres No. 1

SEC. 29 T. 14 R. 10E
SE SE SW

Total Depth. 3313'
Comm. 10-6-58 Comp. 10-17-58
Shot or Treated.
Contractor. White & Ellis Drilling Co.
Issued. 11-15-58

County Wabaunsee
KANSAS



CASING:

3 5/8" @ 207' cem. w/165 sx.

Elevation. 1499' RB

Production. Dry

Figures Indicate Bottom of Formations.

soil	5
red clay & gravel	18
lime	50
lime & shale strks.	155
shale & lime	190
lime	207
shale & lime	405
Gyp. & shale	430
shale	650
lime & lime strks.	800
shale	910
shale & lime	997
shale & lime strks.	1215
lime	1300
lime & shale strks.	1400
lime & shale	1435
sand & sandy shale	1600
shale & lime strks.	1653
lime	1748
shale	1806
lime	2001
shale & lime strks.	2589
chert	2605
lime	2912
shale	2914
shale & shells	3040
shale	3065
lime	3184
shale	3266
lime	3313
Total Depth	

APR 16 1971

Core #1 3256-3268
Core #2 3269-3284

TOPS:

Lansing	1653
Kansas City	1806
Base/Kansas City (Scout)	2000
Mississippi	2589
Kinderhook	2912
Hunton	3065
Wauoketa (Scout)	3184
Wolia	3266