

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

X Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Samson Resources Company

API NO. 15-191-21, 324 0000

ADDRESS 2700 First National Tower

COUNTY Sumner

Tulsa, OK 74103

FIELD Walta-Stewart

**CONTACT PERSON R. J. Davis

PROD. FORMATION Simpson

PHONE 918-583-1791

LEASE Stewart

PURCHASER Total Petroleum, Inc.

WELL NO. 3

ADDRESS 6701 North Broadway

WELL LOCATION SE NW SW

Oklahoma City, OK 73116

990 Ft. from West Line and

DRILLING Ramco Drilling Company

1650 Ft. from South Line of

CONTRACTOR

ADDRESS P. O. Box 204, 100 S. Main

the SW/4 SEC. 19 TWP. 33S RGE. 3W

Wichita, KS 67202

WELL FLAT

PLUGGING

CONTRACTOR

ADDRESS

		19	
0			

KCC
KGS
(Office Use)

TOTAL DEPTH 4590 PBD 4561

SPUD DATE 8-26-81 DATE COMPLETED 9-3-81

ELEV: GR 1234 DF KB 1242

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 273' 8-5/8" DV Tool Used? No

AFFIDAVIT

STATE OF Oklahoma, COUNTY OF Tulsa SS, I,

R. J. Davis

OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Representative (FOR)(OF) Samson Resources Company

OPERATOR OF THE Stewart LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 3 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 17th DAY OF September, 1981, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 22nd DAY OF December, 1981

(S) R. J. Davis

Shonda Kay Yarbrough
NOTARY PUBLIC
12-28-81

MY COMMISSION EXPIRES: September 24, 1985

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
See Attached				

RELEASED
SEP 01 1983
FROM CONFIDENTIAL

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24#	267	Common	200	1/2# / Floucel + 3% CC
Production	7 7/8	5 1/2	14#	4589	Common	125	10% salt, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			2	Great Guns SSB	4537-42

Size	Setting depth	Packer set at
2-3/8"	4523	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
9-17-81	Pumping	47.0

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	48 bbls.	--	11 MCF %	-- CFPD

Disposition of gas (vented, used on lease or sold)	Perforations
Vented	4537-42

W E L L L O G

WELL NAME: Stewart #3

OPERATOR: Samson Resources

SPUD DATE: 8-26-81

CONTRACTOR: Ramco Drilling Company

COMPLETION DATE: 9-4-81

CASING: 8 5/8, 24# new, set @ 273'
w/200 sx cmn, 1/2# Flow seal, 3% cc

LOCATION: SE NW SW
Sec. 19-33S-3w
Sumner County

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface	0	273
Sand	273	700
Sand	700	1220
Sand and Shale	1220	1450
Shale w/Lime Speck	1450	1782
Shale and Lime Specks	1782	2096
Shale and Lime	2096	3319
Lime and Shale	3319	3835
Shale and Lime	3835	4115
Mississippi Lime	4115	4215
Lime and Shale	4215	4490
Smpson	4490	4590
RTD	4590	

RELEASED
SEP 01 1983
FROM CONFIDENTIAL

State Geological Survey
WICHITA BRANCH

STATE OF KANSAS
COUNTY OF SEDGWICK

I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION

By: *[Signature]*

Subscribed and sworn to before me on this 25th day of September, 1981.

JUANITA L. BOTKIN
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Appt. Exp. 6-30-83

Juanita L. Botkin
Notary Public

My Appointment Expires: _____