

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Geoson Oil Co. 16285 API NO. 15-077-20,758-0000
 ADDRESS 212 N. Market, Suite 508 COUNTY Harper
Wichita, Ks. 67202 FIELD Spivey-Grabbs
 **CONTACT PERSON George Ewonus LEASE Sanders

PHONE 316-267-5822
 PURCHASER Peoples Natural Gas Company WELL NO. 1
 ADDRESS 25 Main Place WELL LOCATION NE NE NW
Council Bluffs, Iowa 330 Ft. from North Line and
 330 Ft. from East Line of

DRILLING CONTRACTOR Leben Drilling Co. the SEC. 19 TWP. 31S RGE. 8W
 ADDRESS 105 S. Broadway, Suite 640

Wichita, Kansas 67202-4260

PLUGGING CONTRACTOR _____
 ADDRESS _____

TOTAL DEPTH 4460 PBSD ---
 SPUD DATE 12-27-81 DATE COMPLETED 1-7-82

ELEV: GR1601DF KB 8

DRILLED WITH (~~RAMM~~) (ROTARY) (~~API~~) TOOLS (New) / (~~Used~~) casing.
 Report of all strings set— surface, intermediate, production, etc.

WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC
 KGS

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	286	Common	225	2% gel, 3% CaCl
Production	7 7/8	4 1/2	9 1/2	4355	RFC	125	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2	3 1/2" J. J.	4377-4387'
Size 2 3/8"	Setting depth 4384'	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZING RECORD	
Amount and kind of material used	Depth interval treated
Acidized with 1250 gal Mud Acid	4377-4387'
Fraced with 38,000 gal 1 1/2 gel acid water and 20,000 lbs. sand	4377-4387'

TEST DATE:		PRODUCTION	
Date of first production 6-18-82	Producing method (flowing, pumping, gas lift, etc.) Flowing	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil 4 bbls.	Gas 500 MCF	Water 75 BWPB bbls.
Disposition of gas (vented, used on lease or sold) pipeline		Gas-oil ratio 125,000/1 CFPP	
		Producing interval (ft) 4377-4387'	

** The person who can be reached by phone regarding any questions concerning this information.

A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

STATE RECEIVED
 10-22-82
 OCT 22 1982
 CONSERVATION DIVISION
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION

OCT 21 1982
 10-21-82
 CONSERVATION DIVISION
 Wichita, Kansas

Name of lowest fresh water producing stratum _____ Depth _____
 Estimated height of cement behind pipe 3400'

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0	288		
Shale and Sand	288	1810		
Shale and Lime	1810	3873		
Lime	3873	4353		
Lime	4403	4460	Top Miss	4384-4403

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS,

George Ewonus OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS


OATH, DEPOSES AND SAYS:

THAT HE IS authorized agent FOR Geoson Oil Co., Inc.
 OPERATOR OF THE Sanders LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS
 BEEN COMPLETED AS OF THE 18th DAY OF June 1982, AND THAT ALL
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) George Ewonus
 George Ewonus

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15th DAY OF October 1982



Rita Jeter
 NOTARY PUBLIC Rita Jeter

MY COMMISSION EXPIRES: March 25, 1985