

Original - State Corporation Commission ✓
 1 Copy - Von Roe
 1 Copy - OK City Office
 1 Copy - File


FORM CP-4

15-077-20506-0000

STATE OF KANSAS
 STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to
 Conservation Division
 State Corporation Comm.
 245 North Water
 Wichita, KS 67202



Locate well correctly on above
 Section Plat

Harper County, Sec. 18 Twp. 31 Rge. 6 XB/W
 Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____
 Approx. 150' FSL & 150' FWL SW SE SW
 Lease Owner Phillips Petroleum Co. (former owner Aladdin Petroleum Corp.)
 Lease Name Schultz Well No. 1-A
 Office Address Box 287, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole) _____
Oil

Date Well completed September 14, 1977
 Application for plugging filed February 16, 1978
 Application for plugging approved February 21, 1978
 Plugging commenced March 5, 1978
 Plugging completed March 10, 1978
 Reason for abandonment of well or producing formation _____
Completion method failed - large vol. of water encountered.
 If a producing well is abandoned, date of last production _____
 -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	318'	8 5/8		
	Oil & Water		4809'	5 1/2		


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. 03-05-78 MIRU Toland & Johnson Inc. Mixed 35 sx reg. cmt., pumped down 5 1/2" csg., displ. w/9# mud. Top cmt. 4085' SLM. Shot 5 1/2" csg. @ 3817', LD 87 jts. 5 1/2" 14# csg. Pulled 1 jt. 5 1/2", mixed 35 sx reg. cmt. & spotted @ top 268' to 357'. Pld. 8 jts. 5 1/2" (total 96 jts.) 14# - approx. 3817'. Bridged 8 5/8" 35 to 33', mixed 10 sx common cmt. to surface. Cut 8 5/8" pipe 3' below surf. Welded on steel plate. P&A 03-10-78.

RECEIVED
 STATE CORPORATION COMMISSION
 6-16-78
 JUN 16 1978

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Toland & Johnson, Inc., Oklahoma City, Oklahoma 73109

STATE OF Kansas COUNTY OF Barton ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) C. D. Dohrer Dist. Superintendent
 Box 287, Great Bend, Kansas 67530
 (Address)

Witnessed and sworn to before me this 15th day of June, 1978

March 18, 1980
Velma L. Spanier Notary Public

WELL LOG

0'	-	350'	Surface
350'	-	1415'	lime & shale
1415'	-	2165'	lime & shale
2165'	-	2915'	lime & shale
2915'	-	4301'	lime & shale
4301'	-	4548'	Mississippi
4548'	-	4669'	Kinderhook
4669'	-	4800'	Simpson
4800'	-	4818'	Knuckle
4818'			Total Depth

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1978
2-2178
CONSERVATION DIVISION
Wichita, Kansas