


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County. Sec. 2 Twp. 31 Rge. (E) 7(W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines SW SW SE
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Chevraux Well No. 1
Office Address 522 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-4-57 19
Application for plugging filed 8-5-57 19
Application for plugging approved 8-5-57 19
Plugging commenced 8-5-57 19
Plugging completed 8-5-57 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud to 240, hulls, plug, 20 sacks cement thru drill pipe. Mud to 35', hulls, plug, cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 57

My commission expires June 4, 1959

[Signature] Notary Public.
STATE OF KANSAS

PLUGGING
FILE SEC. 2 T. 31 R. 1W
BOOK PAGE 34 L. 7

AUG 13 1957
8-13-57
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Chevraux
 SW SW SW, Sec. 2-31-7W,
 Harper County, Kansas
 Commenced: 7-20-57
 Completed: 8-4-57
 Contractor: Rupp-Ferguson Oil Co.

Elev. 1559 M
 B & A.

Set 250' of 2 5/8" surface csg. w/150 max

Figures Indicate Bottom of Formation

27 surface soil & sand
 43 red bed
 53 sand & gravel
 810 red bed
 850 red bed, shale, shells
 910 red bed, Anhy., shells & shells
 1175 salt, shale
 1640 lime & shale
 1730 lime streaks
 1925 shale & lime
 2425 shale
 2925 shale & shells
 3097 lime & shale
 3500 sandy shale & lime
 3645 sand & shale
 3750 shale & lime
 3920 lime
 3935 shale & lime
 4024 lime
 4104 lime & shale
 4244 lime
 4307 shale & lime & streaks Pyrite
 4315 lime & shale
 4340 Miss.
 4377 Miss. cherty
 4425 Miss.
 4500 lime
 4570 Miss.
 4615 lime & shale
 4675 shale
 4720 lime & shale-4735 Simpson
 4815 Simpson shale & sand streaks
 4875 Arb. T.B.

(STATE OF KANSAS)
 HARPER COUNTY) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Chevraux.

RECEIVED
 STATE CORPORATION COMMISSION

PLUGGING			
FILE	SEC	T	R. 7W
BOOK	PAGE	34	LINE 7

AUG 13 1957
 8-13-57
 ENGINEER REGULATION DIVISION
 Topeka, Kansas

L. W. Knox
 L. W. Knox

Subscribed and sworn to before me this 12th day of August, 1957.

My Commission Expires June 4, 1959.

Helen Ferine
 Notary Public