

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-077-20560-0000

LEASE NAME Smith

WELL NUMBER No. 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 2 TWP. 31 RGE. 7W (E or W)

COUNTY Harper

Date Well Completed 12-29-79

Plugging Commenced 4-18-87

Plugging Completed 4-20-87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Gressel Corporation

ADDRESS P.O. Box 322 Haysville, Kansas 67060

PHONE# (316) 773-1248 OPERATORS LICENSE NO. 5822

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Wichita

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4297 Bottom 4332 T.D. 4350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	Water	3775	4010	8 5/8	252	None
Mississippi	Water and Oil	4297	4350	4 1/2	4359	3199

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
4359 to 3199-4 1/2 casing in hole with 2" tubing stuck in casing, rods in tubing full of sand. Mud 3199 to 560. Rock bridge 560 to 530 readymix cement 530 to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corporation License No. 5822

Address P.O. Box 322 Haysville, Kansas 67060

STATE OF Kansas COUNTY OF Sedgewick, ss.

Dewey Gressel (Gressel Corporation) (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dewey Gressel

(Address) Box 322 Haysville, KS

SUBSCRIBED AND SWORN TO before me this 27 day of April, 19 87

My Commission Expires: 6/12/89 STATE CORPORATION COMMISSION



APR 28 1987  
 4-28-87  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-077-20560-0000

W. PAT SIMMONS

PETROLEUM  
GEOLOGIST

DRILLING PROSPECTS — OIL & GAS INVESTIGATIONS — WELL SUPERVISION — WELL COMPLETIONS  
5252 NORTH BROADWAY ● WICHITA, KANSAS 67219 ● 316 838-3761

December 31, 1979

GEOLOGIC REPORT

Indian Wells Oil Company  
Smith # 1  
C SW SW Section 2-31S-7W  
Harper County, Kansas

Elevation: 1551 RB  
Commenced: 12/14/79  
Completed: 12/29/79

Casing Record

8 5/8" @ 252'/225 sax.  
4 1/2" @ 4349'/150 sax.

Development well - I. P. Pending

SUMMARY OF FORMATIONS

Heebner	3252 (-1701)
Stalnaker Sand	3559 (-2008)
Base of Stalnaker Sand	3643 (-2092)
Kansas City	3775 (-2224)
Hertha Zone	3920 (-2369)
Swope Zone	3956 (-2405)
Base of Kansas City	4010 (-2459)
Erosional Mississippian	4297 (-2746)
Mississippian Pay Zone	4320 (-2769)
Rotary Total Depth	4350 (-2799)

CORES: None

ELECTRIC LOGS: A Gamma Ray-Neutron-Radiation Guard with Density Log was run to total depth. Depths checked within 3 feet of the Drillers measurements.

DRILL STEM TESTS: # 1 (4302-4313) Tool open for 1 hour. Strong blow throughout test. Recovered 80 feet of slightly gas cut mud. No shows of oil. IBHP 413# FBHP 476# IFP 63# FFP 84#.

# 2 (4310-4330) Tool open for 1 hour. Gas to surface in 15 minutes. Guage 110,000 CFPD at the end of 1 hour. Recovered 310 feet of fluid; (190 feet of HO + GCM - 120 feet of muddy oil). IBHP 1123# FBHP 987# IFP 137# FFP 169#.

SUMMARY OF OIL SHOWS

STALNAKER: None

KANSAS CITY: None

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1980  
4-20-87  
CONSERVATION DIVISION  
Wichita, Kansas