

API NUMBER 15-077-20,6070000

LEASE NAME Oscar Smith

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from N Section Line

660 Ft. from E Section Line

SEC. 2 TWP. 31 RGE. 7 (E) or (W)

COUNTY HARPER

Date Well Completed 10-29-00

Plugging Commenced 11-27-00

Plugging Completed 11-28-00

LEASE OPERATOR MTM Petroleum, Inc.

P.O. Box 82
ADDRESS 160 S. Main, P.O. Box 7, Spivey, Ks. 67142

PHONE(S) (916) 532-3794 OPERATORS LICENSE NO. 6236

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-25-00 (date)

by Steve Van Giesen (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? See attached

Producing Formation Miss. Depth to Top 2738 Bottom 4340 T.O. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Miss.</u>	<u>4340</u>	<u>4340</u>	<u>2738</u>			
<u>Kansas City</u>		<u>3806</u>		<u>8 5/8</u>	<u>238'</u>	
<u>Stalnaker</u>		<u>3236</u>		<u>4 1/2</u>	<u>4400'</u>	<u>2127'</u>
<u>Heebner</u>		<u>3293</u>				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Sanded bottom. Loaded hole. shot 2127'. Pulled to 1,300'. Pumped 35 sacks.
Pulled to 850'. Pumped 35 sacks. pulled to 300'. Circulated cement to the surface. Hole stayed full.

Name of Plugging Contractor Quality Well Service License RECEIVED 12-21-00

Address 415 E. Main St., Sterling, Ks. 67579 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MTM Petroleum DEC 21 2000


STATE OF Kansas COUNTY OF Kingman, ss. 12-21-00

Marvin A. Miller, Operator (Employee of Operator) CONSERVATION DIVISION
Wichita, Kansas

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well is filled and the same are true and correct, so help me God.

(Signature) Marvin A. Miller

(Address) P.O. Box 82, Spivey Ks 67142



SUBSCRIBED AND SWORN TO before me this 13th day of December, 2000

Kathy Hill
Notary Public

My Commission Expires: 01-04-2003

USE ONLY ONE SIDE OF EACH FORM



2-3-61

STATE KANSAS CO. HARPER MAPNO. S-T-R 2-31S-7W D
 OPER. ELDON J SCHIERLING 830 SUTTON PLACE, WICHITA, KS 67202 LOC. C NW NE INIT.
 WELL 1 OSCAR SMITH
 CONTR. GABBERT JONES ELEV. 1602 KB, 1597 GR DG
 FIELD MAPLE GROVE S (LANS) SUB STRUCTURE FIN.
 IP 4 PT CAOF 600 MCFGPD (MISS) 4342-46
 API 15-077-20607-~~680~~ FR 7-28-80 COMP. ISSUED 2-17-81

SPUD 10-20-80, 8 5/8 @ 238 w/230
 DST 1 (MISS) 4332-42, op30,si45,op45,si45, GTS/8", F 156
 MCFG/10", 2nd op F 251 MCFG, rec 70'mud, ISIP 1454,
 FP 72-52,104-72, FSIP 1433
 DST 2 (MISS) 4342-52, op30,si45,op45,si45, GTS/13" F 113
 MCFG, 2nd op F 175 MCFG, rec 180'mud, 65'WCM, ISIP
 1454, FP 104-83,83-83, FSIP 1454
 RTD 4402, log (10-29-80) 4 1/2 @ 4400 w/125
 Perf (MISS) 4342-46 w/4 spf, 500 GA
 4 PT CAOF 600 MCFGPD (MISS) 4342-46
 COMPLETED 1-30-81

KB LOG TOPS
 HEEBNER 3293 - 1691
 STALNAKER 3636 - 2034
 KANSAS CITY 3803 - 2201
 SWOPE 3944 - 2342
 HERTHA 3976 - 2374
 MISS 4340 - 2738
 RTD 4402 - 2800
 TD IN MISS

 Petroleum Information Corporation
 A Subsidiary of A. C. Nielsen Company
 © Copyrighted 1981 Reproduction Prohibited

RECEIVED
 STATE CORPORATION COMMISSION

DEC 21 2009
 12-21-09
 CONSERVATION DIVISION
 Wichita, Kansas